

WATER SERVICE REQUIREMENTS FOR SENECA FALLS

- 1. The pipe being installed is to be ¾" K-Copper or 1" CTS PVC Larger pipe with the approval from the Seneca Falls Water Department.**
- 2. If CTS PVC is installed, it is to be bedded & covered with sand and have a trace wire run alongside the pipe.**
- 3. All water fittings before the meter will be brass with either flared or compression style nuts intended for in ground use.**
- 4. There will be no fittings between the curb stop and the water meter. This means that there has to be a solid length of pipe between the curb stop and water meter unless approved by the Water Department.**
- 5. The meter will be installed in a horizontal position with a shut-off valve before and after the meter closes to the front wall as possible.**
- 6. There will be NO "sweat" style, steel or PVC fittings before the water meter, only compression type or flare type fittings.**
- 7. The water service is to be buried at a depth of 4'6" to the top of the pipe.**
- 8. NO ONE is to operate the curb stop except for the Town of Seneca Falls Water Department Personnel.**
- 9. All work done to the water system is to be inspected by the Seneca Falls Water Department between the hours of 7am-3pm. Any work done on weekends/after business hours/or on holidays will still need to be inspected before backfilling. The homeowner/contractor will be billed a minimum of 3 hours for EACH call-out (after hours) for inspection. AN APPOINTMENT NEEDS TO BE SCHEDULED 24 HOURS IN ADVANCE THROUGH THE WATER OFFICE. 315.568.6211**
- 10. Water Service will NOT be restored unless all work has been inspected by the Town of Seneca Falls Water Department.**